

- Option 2: crushed rock material (3/4" minimum size to 1-1/2" maximum size) must be on site at the time of bottom inspection for hole verification. No special inspection required.
- When pool coping is removed, it shall be removed to a minimum depth of 18 inches below the finished grade. (Removal of the coping is not a requirement.)
- All gas, water, and sewer lines to the pool shall be securely capped off with an approved fitting.
- All electrical pool equipment, including the breaker in the electrical panel, shall be removed.
- Removal of all above ground pool plumbing including pumps and heaters is required.
- Final
 - If utilizing option 1 for backfill, special inspection report is required at Final – 90% compaction required.
 - Site shall be clean of all debris and material
 - Site shall be graded away from building and conform to site drainage.